

Maxwell Insulated and Pre-flared Refrigerant Tubing with Interconnecting Electrical Wires



Fitted with pre-flared couplings

Sizes: 1/4 x 3/8; 1/4 x 1/2; 1/4 x 5/8; 3/8 x 5/8

Available lengths: 15', 25', 33' and 50 feet.

Class 0 copper tubing in conformity with standard ASTM B280

Factory direct with precise flared couplings prevents gas leakage during installation & operation.

Excellent quality white PE foam insulation which prevents condensation during the air conditioner operation.

Packed in a plastic bag with moisture absorption grain.

WHAT'S INCLUDED

- Wall Sleeve Cylinder
- Decorative Wall Cap
- Wall Filler Putty
- Non-Adhesive Decorative Wrapping Tape
- 6 ft. Long Flexible Condensate Drain Hose
- Matching Length of Stranded and Unshielded 4 x 16 AWG 4 Lead Interconnecting Cable

